



**Request for Proposals for Fiber Testing
 Presque Isle Electric & Gas Co-op (PIE&G)
 ADDENDUM #1 – RESPONDENT Q&A**

This addendum is hereby incorporated into the above-referenced Request for Proposals. The following items are clarifications, corrections, additions, deletions and/or revisions to and shall take precedence over the original documents. If applicable, additions are indicated by underlining, deletions are indicated by ~~strikethrough~~.

RESPONDENT QUESTIONS:

PIE&G received the following questions (slightly revised for clarity) from prospective Respondents and provides the following answers:

No.	Question	Answer
1	Is there an estimated quantity of ports/projects?	Yes. Estimated at no more than 9 hut sites and no more than 5,000 fibers to test.
2	What is the required timeframe for the project (start date and completion deadline)?	Testing must be completed by August 1, 2026.
3	Are there liquidated damages?	Failure to complete testing by August 1, 2026 shall result in liquidated damages of \$1,000 per day. Typical Force Majeure allowances will be included in the contract.
4	Will this be only end to end testing? Or is this an FTTH system to consider the need of aerial locations?	Testing will be from the hut end locations only. Outside plant field terminated fibers will be excluded from bidirectional testing requirements.
5	What style of connectors are used within your system?	SC/APC, LC/UPC, SC/UPC
6	If field/aerial locations need to be tested, will necessary traffic control be a passthrough to owner?	Head end locations provide off-street parking; no traffic control is required.
7	Is this project subject to the Davis Bacon Wage Act or State Prevailing Wages?	No.
8	If you have various styles of systems, will all needed testing be only 1550/1310 NM? Or will there be a need for CWDEM and/or DWDM wavelength testing?	Only 1550/1310 NM testing is needed.

**** END OF ADDENDUM #1 ****